ROYALTY CALCULATION				
Name of work :Improvements to Roads and drains in Vinayaka nagara and Sorrounding Area in ward No: 14 Dasarahalli Sub division				
Plain Cement Concrete 1:4:8				
Description	Qty in Cum	Constant	Total Qty	
Sand	31.02	0.57	17.68	
Jelly	31.02	0.85	26.37	
Cement Concrete M20				
Sand	69.22	0.46	31.84	
Jelly	69.22	0.69	47.76	
Precast Concrete Slab 100mm thick				
Sand	16.92	0.47	7.95	
Jelly	16.92	0.70	11.84	
Sl	Items	Qty	Rate	Amount
1	Sand	57.48 X	138 =	7932-00
2	Jelly	85.97 X	126 =	10832-00
			Total	18,764-00

Asst.Engineer
Bagalagunte Ward No 14

Asst.Executive Engineer
T.Dasarahalli Sub Division